
FINDLAY CREEK BOARDWALK EXTENSION

OTTAWA, ONTARIO

CONTRACT No.: 22-1042A





DWG No.	DRAWING NAME	REV No
	COVER	0
LEG	LEGEND	0
ALI.1	ALIGNMENT OF BOARDWALK	0
DET.1	DETAILS - CIVIL	0
REM.1	REMOVALS AND REINSTATEMENTS	0
S001	STRUCTURAL NOTES, KEY PLAN	0
S002	BOARDWALK TYP. SECTIONS	0
S003	TYP. SLOPE SECTIONS, BUMP OUTS PLAN & SECTION	0
S004	FRAMING PLAN AT BOARDWALK VIEWING PLATFORM	0
S005	BRIDGE PLAN, SECTIONS & DETAILS	0
L-1	LANDSCAPE PLAN	0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
		0
	+	0



12 INTERNATIONAL DRIVE, PEMBROKE, ON Phone: (613)735-2507, Fax:(613)735-4513

1150 MORRISON DRIVE, SUITE 410, OTTAWA, ON Phone: (613)828-7800, Fax: (613)828-2600

16 EDWARDS STREET SOUTH, UNIT 53B, ARNPRIOR, ON

Jp2g PROJECT No: 22-1042A

GENERAL NOTES

- 1. LIDAR INFORMATION RECEIVED FROM SNC. THE PROJECTION IS ONTARIO MTM ZONE 9, NAD83 (CSRS).
- 2. DO NOT SCALE DRAWINGS.
- 3. THE CONTRACTOR IS RESPONSIBLE FOR CHECKING AND VERIFYING ALL DIMENSIONS WITH RESPECT TO SITE CONDITIONS AND ALL MATERIALS TO THE PROJECT. ANY DISCREPANCIES SHALL BE REPORTED TO THE FNGINFER.
- 4. CONTRACTOR MUST COMPLY WITH LOCAL BY-LAWS, CANADIAN CONSTRUCTION SAFETY CODE AND ALL REGULATIONS SET BY AUTHORITIES HAVING JURISDICTION. IN CASE OF CONFLICT OR DISCREPANCY, THE MORE STRINGENT REQUIREMENTS SHALL APPLY.
- 5. CONTRACTOR RESPONSIBLE FOR OBTAINING ALL REQUIRED UTILITY LOCATES, INSPECTIONS, PERMITS, AND APPROVALS, INCLUDING ALL ASSOCIATED COSTS.
- 6. ALL LOCATIONS AND ELEVATIONS OF EXISTING SERVICE AND UTILITIES SHOWN ON THE PLANS ARE BASED ON BEST AVAILABLE INFORMATION AND FOR REFERENCE PURPOSES ONLY. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND PROTECTING ALL UTILITIES DURING CONSTRUCTION.
- 7. ALL TRENCHING IS TO BE DONE IN ACCORDANCE WITH THE CONSTRUCTION SAFETY ACT.
- 8. ALL WORK SHALL BE IN ACCORDANCE WITH CURRENT ONTARIO PROVINCIAL STANDARD DRAWING SPECIFICATIONS UNLESS OTHERWISE NOTED.
- 9. PROPERTY BOUNDARIES SHOWN ON THE PLANS ARE FROM GIS DATA PROPERTY BOUNDARIES AS SHOWN ARE APPROXIMATE AND AND ARE APPROXIMATE. CONTRACTOR TO CONFIRM PROPERTY BOUNDARIES IN THE FIELD AND COORDINATE WITH THE LAND OWNERS FOR SITE ACCESS.
- 10. WORK SHOULD BE UNDERTAKEN DURING A SEASONALLY DRY PERIOD.
- 11. KEEP EXCAVATIONS FREE OF WATER WHILE WORK IS IN PROGRESS.
 DEWATERING SHALL BE ACCORDING TO OPSS 517.
- 12. CONTRACTOR TO REINSTATE TO MATCH EXISTING CONDITIONS WHILE PROVIDING POSITIVE DRAINAGE (MIN 2%) AWAY FROM PATHWAY TO DRAINAGE DITCHES OR WATERCOURSE.
- 13. ENSURE UNOBSTRUCTED DRAINAGE IS MAINTAINED ALONG TRAIL CORRIDOR.
- 14. NO IN WATER WORK SHALL BE COMPLETED DURING THE FISH SPAWNING PERIOD (MARCH 15 JULY 1).
- 15. CONTRACTOR TO COMPLETE WORK OUTSIDE OF BIRD NESTING PERIOD, MID APRIL LATE AUGUST (ZONE C3 & C4)
- 16. CONTRACTOR TO COMPLETE WORK OUTSIDE OF TURTLE NESTING PERIOD (MAY MID JULY).


ENVIRONMENTAL PROTECTION

- 1. THE CONTRACTOR SHALL PROVIDE EROSION AND SEDIMENT CONTROL PLAN FOR APPROVAL PRIOR TO COMMENCING WORK. THE PLAN SHALL IMPLEMENT BEST MANAGEMENT PRACTICES TO PROVIDE FOR PROTECTION OF THE AREA DRAINAGE AND THE RECEIVING WATER COURSE, DURING CONSTRUCTION ACTIVITIES; THIS INCLUDES LIMITING THE AMOUNT OF EXPOSED SOIL, INSTALLING SILT FENCES AND OTHER EFFECTIVE SEDIMENT TRAPS, AND INSTALLING AND MAINTAINING MUD MATS FOR OUTGOING CONSTRUCTION TRAFFIC DURING CONSTRUCTION ACTIVITIES.
- 3. PREVENT SOIL LOSS DURING CONSTRUCTION (BY STORM WATER RUNOFF OR WIND EROSION). RUN-OFF FROM CONSTRUCTION MATERIALS AND ANY STOCKPILES SHALL BE CONTAINED AND DISCHARGED SO AS TO PREVENT THE ENTRY OF SEDIMENT TO WATERCOURSES.
- 4. SEDIMENT AND EROSION CONTROL MEASURES MAY BE MODIFIED TO SUIT FIELD CONDITIONS.
- 5. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENTATION CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
- 6. EROSION AND SEDIMENT FEATURES SHOWN ON PLAN ARE FOR REFERENCE ONLY. CONTRACTOR SHALL MONITOR AND MAINTAIN EROSION AND SEDIMENTATION CONTROL MEASURES TO ENSURE THEY PERFORM AS INTENDED.
- . NATIVE SEED MIXTURE TO BE USED WHERE GRASS REINSTATEMENT IS REQUIRED.
- 8. FINAL SURFACE TREATMENT TO MATCH PRE-ADJACENT LAND CONDITIONS.
- 9. TREE REMOVAL SHALL BE AVOIDED, MINOR ADJUSTMENTS TO ALIGNMENT MAY BE REQUIRED.
- 10. THE CONTRACTOR SHALL MINIMIZE DISTURBANCE OUTSIDE TRAIL CORRIDOR. ALL DISTURBED AREAS MUST BE REINSTATED TO THIS PRE-CONSTRUCTION CONDITION.
- 11. ALL MATERIAL AND EQUIPMENT TO BE STORED OUTSIDE THE 1:100 YEAR FLOODPLAIN.
- 12. PROPOSED STOCKPILE LOCATIONS SUBJECT TO APPROVAL BY APPROPRIATE LANDOWNERS AND SNCA.

DEWATERING NOTES

 CONTRACTOR TO VERIFY THAT CONSTRUCTION CAN BE COMPLETED IN THE DRY. IF SO, THE CONTRACTOR MAY USE OTHER METHODS FOR DEWATERING. IF THE WORK CANNOT BE COMPLETED IN THE DRY, THE FOLLOWING STEPS MUST BE IMPLEMENTED.

LEGEND STANDARD IRON BAR TOTAL STATION POINT APPROXIMATE BORE HOLE LOCATION EXISTING SIGN EXISTING BOULDER EXISTING POLE EXISTING SANITARY MANHOLE EXISTING DITCH INLET EXISTING HYDRO POLE EXISTING ANCHOR EXISTING STAKE × 100.00 EXISTING ELEVATIONS ×100.00 PROPOSED ELEVATIONS EXISTING TREE PROPOSED LANDSCAPE FEATURE - BOULDE PROPERTY LINE (APPROX.) EXISTING TOE OF SLOPE EXISTING TOP OF BANK \rightarrow \longrightarrow \longrightarrow \longrightarrow EXISTING SWALE EXISTING DITCHLINE



SILT FENCE BARRIER PER OPSD 219.110

FINDLAY CREEK BOARDWALK EXTENSTION OTTAWA, ONTARIO

SOUTH NATION

DE LA NATION SUD

AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE

SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

PROJECT LOCATION -

KEYPLAN (NTS)

CONTRACT DRAWING, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, THE CONTRACTO

DESIGN PROFESSIONAL'S SEAL OR SIGNATURE IS EFFECTIVE ONLY AS TO THAT VERSION OF THIS DOCUMENT AS ORIGINALLY PUBLISHED BY DESIGN PROFESSIONAL. DESIGN PROFESSIONAL IS NOT RESPONSIBLE FOR ANY SUBSEQUENT MODIFICATION, CORRUPTION, OR UNAUTHORIZED USE OF SUCH DOCUMENT. TO VERIFY THE VALIDITY OR APPLICABILITY OF THE

CONSERVATION

INDEX



12 INTERNATIONAL DRIVE, PEMBROKE, ON Phone: (613)735-2507, Fax:(613)735-4513 1150 MORRISON DRIVE, SUITE 410, OTTAWA, ON Phone: (613)828-7800, Fax: (613)828-2600

Jp2g Project No.: 22-1042A

CLIENT No.: 22-1042A

SCALE:

DESIGNED: SA

DRAFTED: MW


CHECKED: SA


APPROVED: XX


LEG.

OVER PAGE & INDEX.DWG












THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWING, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

DESIGN PROFESSIONAL'S SEAL OR SIGNATURE IS EFFECTIVE ONLY AS TO THAT VERSION OF THIS DOCUMENT AS ORIGINALLY PUBLISHED BY DESIGN PROFESSIONAL. DESIGN PROFESSIONAL IS NOT RESPONSIBLE FOR ANY SUBSEQUENT MODIFICATION, CORRUPTION, OR UNAUTHORIZED USE OF SUCH DOCUMENT. TO VERIFY THE VALIDITY OR APPLICABILITY OF THE



SCALE: NTS

KEYPLAN (NTS)

1	2022-10-11	SA	50% SUBMISSION	
2	2022-11-11	SA	90% SUBMISSION	
No.	YYYY-MM-DD	BY	REVISION COMMENTS	

FINDLAY CREEK BOARDWALK EXTENSTION OTTAWA, ONTARIO

DETAILS



Phone: (613)735-2507, Fax:(613)73 1150 MORRISON DRIVE, SUITE 410, OTTA Phone: (613)828-7800, Fax: (613)83

CLIENT No.: 22-1042A SCALE:

DESIGNED: SA


DRAFTED: MW


CHECKED: SA


APPROVED: XX

DET.1

DE.










THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWING, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

DESIGN PROFESSIONAL'S SEAL OR SIGNATURE IS EFFECTIVE ONLY AS TO THAT VERSION OF THIS DOCUMENT AS ORIGINALLY PUBLISHED BY DESIGN PROFESSIONAL. DESIGN PROFESSIONAL IS NOT RESPONSIBLE FOR ANY SUBSEQUENT MODIFICATION, CORRUPTION, OR UNAUTHORIZED USE OF SUCH DOCUMENT. TO VERIFY THE VALIDITY OR APPLICABILITY OF THE



KEYPLAN (NTS)

1 2022-10-11 SA 50% SUBMISSION
2 2022-11-11 SA 90% SUBMISSION

No. YYYY-MM-DD BY REVISION COMMENTS

FINDLAY CREEK BOARDWALK EXTENSTION OTTAWA, ONTARIO

REMOVALS AND REINSTATEMENTS



12 INTERNATIONAL DRIVE, PEMBRORE, ON Phone: (613)735-2507, Fax:(613)735-4513 1150 MORRISON DRIVE, SUITE 410, OTTAWA, ON Phone: (613)828-7800, Fax: (613)828-2600

CLIENT No.: 22-1042A

DESIGNED: SA

DRAFTED: MW

CHECKED: SA

APPROVED: XX

0 m 4 8 2 6 10 m

REM.1

REMOVALS & REINSTATEMENTS.DWG

GENERAL STRUCTURAL NOTES

- STRUCTURAL DESIGN IS IN ACCORDANCE WITH THE 2012 ONTARIO BUILDING CODE (OBC) SUPPLEMENTED BY THE 2010 NATIONAL BUILDING CODE OF CANADA STRUCTURAL COMMENTARY.
- THIS IS A METRIC PROJECT. UNLESS OTHERWISE NOTED, ALL LENGTHS ARE IN MILLIMETERS.
- REVIEW STRUCTURAL DRAWINGS IN CONJUNCTION WITH ALL OTHER CONTRACT DOCUMENTS. REPORT DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.
- VERIFY EXISTING DIMENSIONS AND CONDITIONS ON SITE PRIOR TO CONSTRUCTION.
- THE REVISION COLUMN INDICATES THE INTENDED USE OF THESE DRAWINGS. DO NOT CONSTRUCT FROM THESE DRAWINGS UNLESS MARKED "ISSUED FOR CONSTRUCTION".
- DO NOT USE INFORMATION ON THESE DRAWINGS FOR ANY OTHER PROJECTS.
- DO NOT SCALE THESE DRAWINGS.
- FOLLOW TYPICAL DETAILS SHOWN ON DRAWINGS, UNLESS OTHERWISE NOTED. TYPICAL DETAILS SHOW STRUCTURAL INTENT RATHER THAN ACTUAL PROJECT CONDITIONS. (NOTE THAT TYPICAL DETAILS ARE NOT ALWAYS REFERENCED ON PLAN.)
- SECTIONS, DETAILS, AND STATEMENTS NOTED AS "TYPICAL" SHALL CONVEY THAT CONDITIONS ARE LIKE OR SIMILAR IN THE STRUCTURE.
- THESE DRAWINGS SHOW THE COMPLETED STRUCTURE ONLY. TEMPORARY WORKS FOR WHICH THE CONTRACTOR IS RESPONSIBLE AND WHICH MAY BE REQUIRED FOR EXECUTION OF THE PROJECT ARE NOT SHOWN. CONSTRUCTION LOADS ON THE PERMANENT STRUCTURE SHALL NOT EXCEED DESIGN LOADS INDICATED ON DRAWINGS.
- ALL TEMPORARY WORKS SHALL BE DESIGNED AND REVIEWED BY A PROFESSIONAL ENGINEER RETAINED BY THE CONTRACTOR, LICENSED IN ONTARIO.
- PROVIDE REASONABLE NOTICE (NOT LESS THAN 24 HOURS) PRIOR TO CONCEALING ANY WORK THAT REQUIRES INSPECTION, REVIEW, OR TESTING. SCHEDULE THIS WORK TO OCCUR DURING NORMAL BUSINESS HOURS.
- PERIODIC FIELD REVIEW OF A REPRESENTATIVE SAMPLE OF THE STRUCTURAL WORK DESIGNED BY JP2G WILL BE UNDERTAKEN TO AS CERTAIN GENERAL CONFORMANCE WITH THE STRUCTURAL DRAWINGS AND SPECIFICATIONS. THESE REVIEWS DO NOT REPLACE THE CONTRACTOR'S RESPONSIBILITY FOR QUALITY CONTROL AND QUALITY ASSURANCE.
- TEMPORARY SHORING REQUIRED IS NOT SHOWN ON STRUCTURAL DRAWINGS. IF REQUIRED, CONTRACTOR AND THEIR ENGINEER SHALL DETERMINE THE TEMPORARY SHORING REQUIREMENTS.

SHOP DRAWINGS

- SUBMIT FOR REVIEW ALL SHOP DRAWINGS REQUIRED BY THESE DRAWINGS AND SPECIFICATIONS. SHOP DRAWINGS FOR REVIEW SHALL INCLUDE BUT NOT BE LIMITED TO:
- 1.1. WOOD CONNECTORS FROM MANUFACTURER OTHER THAN SIMPSON STRONGTIE WOOD PRESERVATIVE/ SEALANT GEOGRID FOR RETAINING WALL
- RETAINING WALL BLOCKS
- REVIEW OF SHOP DRAWINGS IS ON A SAMPLING BASIS, FOR GENERAL CONFORMITY WITH STRUCTURAL CONTRACT DOCUMENTS. IT IS NOT A DETAILED CHECK AND MUST NOT BE CONSTRUED AS RELIEVING THE CONTRACTOR OF RESPONSIBILITY FOR MAKING THE WORK ACCURATE AND IN CONFORMITY WITH THE CONTRACT DOCUMENTS.
- REVIEW OF SHOP DRAWINGS DOES NOT IMPLY ANY CHANGE IN ANY OTHER CONSULTANTS' OR PROFESSIONALS' RESPONSIBILITIES RELATED TO DESIGN OF SPECIFIC ITEMS AS OUTLINED BY THE SPECIFICATIONS.
- REVIEW OF A SPECIFIC COMPONENT ON NON-STRUCTURAL SHOP DRAWINGS (COMPONENTS ENGINEERED BY OTHERS) DOES NOT INCLUDE REVIEW OF THE ASSEMBLY OF WHICH THE ITEM MAY

 18. DECK BOARDS TO BE FASTENED TO FRAMING WITH 75MM (3") LONG DECK SCREWS AT EVERY BE A COMPONENT.
- IF REQUIRED, CAD FILES OF THE FULL SET OF STRUCTURAL DRAWINGS ARE AVAILABLE "AS-IS" FOR CONCRETE USE IN THE PREPARATION OF SHOP DRAWINGS, PROVIDED THAT THE OWNER AND THE OWNER'S CONSULTANTS ARE NOT HELD RESPONSIBLE FOR ANY ERRORS OR OMISSIONS ON THE DRAWINGS. 1. THESE CAD DRAWINGS ARE NOT TO BE SCALED. TO RECEIVE THE CAD FILES, THE CONTRACTOR MUST BE WILLING TO SIGN A DRAWING RELEASE WAIVER.
- ALLOW MORE TIME WHEN LARGE QUANTITIES OF SHOP DRAWINGS ARE SUBMITTED. SUBMIT IN GENERAL CONFORMITY WITH THE SEQUENCE OF CONSTRUCTION INTENDED.
- MAKE CORRECTIONS REQUIRED BY PREVIOUS REVIEW BEFORE RESUBMITTING DRAWINGS. CLEARLY INDICATE ALL CHANGES AND ADDITIONS TO PREVIOUS SUBMISSION. DO NOT ADD NEW DETAILS TO DRAWINGS WHICH HAVE BEEN STAMPED AS REVIEWED OR NOTED.
- AFTER REVIEW, THE DRAWINGS WILL BE STAMPED AND RETURNED TO SHOW ONE OF THE

SHOWS WORK WHICH IS NOT WITHIN THE SCOPE OF STRUCTURAL NOT REVIEWED CONSULTING SERVICES. CONTRACTOR APPEARS TO HAVE INTERPRETED THE CONTRACT

DOCUMENTS CORRECTLY AND THE CONSULTANT HAS NO SPECIFIC COMMENT OR NOTES.

THE CONTRACTOR SHALL ADDRESS THE NOTES FROM THE CONSULTANT PRIOR TO CONSTRUCTION. SUBMIT FINAL RECORD PRINT. REVISE & RESUBMIT ADDRESS COMMENTS AND RESUBMIT FOR REVIEW PRIOR TO FABRICATION.

- SUBMIT ENGINEER SEALED SHOP DRAWINGS WHEN REQUIRED BY SPECIFICATIONS. SHOP DRAWINGS NOT STAMPED, SIGNED, AND DATED WILL BE MARKED "RESUBMIT" AND RETURNED WITHOUT BEING REVIEWED.
- DO NOT COMMENCE FABRICATION UNTIL RETURNED SHOP DRAWINGS HAVE BEEN EXAMINED.

PROVIDE FINAL RECORD DRAWINGS AFTER ALL CORRECTIONS ARE MADE.

WOOD FRAMING

- UNLESS NOTED OTHERWISE, ALL WOOD FRAMING DETAILS TO BE IN ACCORDANCE WITH PART 4 OF
- 2. WOOD STRUCTURE TO BE ASSEMBLED IN DRY CONDITIONS.
- 3. USE ONLY SEASONED LUMBER (MOISTURE CONTENT < 15%)
- 4. DIMENSIONAL LUMBER: USE ONLY NO.2+ GRADE (OR BETTER), SPF (SPRUCE-PINE-FIR), UNLESS INDICATED OTHERWISE
- PRESSURE TREATED WOOD (PT):
- 5.1. ALL WOOD COMPONENTS TO BE PRESSURE TREATED.
- ALL CUT ENDS AND PENETRATIONS OF PRESSURE TREATED WOOD MEMBERS ARE TO BE COATED WITH A WOOD PRESERVATIVE OR SEALER
- 6. WOOD CONNECTORS: ALL CONNECTORS SHOWN ARE BY SIMPSON STRONG TIE. PROVIDE CONNECTORS AS SHOWN, OR THOSE OF EQUIVALENT CAPACITY. FASTEN ALL CONNECTORS AS

 6. LOCATE BASE OF RETAINING WALL AT ELEVATIONS INDICATED ON DRAWINGS... DIRECTED BY MANUFACTURER.
- WOOD BOLTS: ASTM A307
- LAG SCREWS: CSA B34. MACHINE THREADED (NOT CAST-THREADED). PREDRILL PRIOR TO LAG SCREW INSTALLATION.
- 9. NAILS: CSA G40.21, ALL NAILS TO BE COMMON NAILS AND FOLLOW COMMON NAIL LENGTHS AND SHANK DIAMETERS. SUBSTITUTION OF COMMON NAILS WITH POWER DRIVEN NAILS OF THE SAME LENGTH AND DIAMETER IS ACCEPTABLE. SUBSTITUTION OF POWER DRIVEN NAILS OF SMALLER DIAMETER MUST BE APPROVED IN WRITING BY ENGINEER PRIOR TO USE. POWER DRIVEN NAILS NOT TO BE OVER-DRIVEN INTO WOOD OR SHEATHING.
- 10. IF GALVANIZED CONNECTORS ARE USED, HOT DIP GALVANIZING: ASTM A123/A123M, MINIMUM ZINC COATING OF 610 g/m²., UNLESS NOTED OTHERWISE. ALL STEEL CONNECTORS TO BE STAINLESS OR GALVANIZED.
- PROTECT ALL WOOD PRODUCTS FROM THE ELEMENTS AS REQUIRED TO MAINTAIN THEIR

TO MEET DESIGN WITHOUT DETERRING FROM ORIGINAL DESIGN INTENT.

- 12. PROVIDE ALL ERECTION BRACING REQUIRED TO KEEP THE STRUCTURE STABLE AND IN ALIGNMENT DURING CONSTRUCTION.
- 13. MEMBER SIZES INDICATED ON DRAWINGS ARE A MINIMUM AND MAY BE INCREASED AS REQUIRED
- 14. NOTCHING AND DRILLING OF FRAMING MEMBERS THAT DO NOT CONFORM TO PART 4 OF THE REFERENCED BUILDING CODE MUST BE REVIEWED BY THE ENGINEER RESPONSIBLE FOR THOSE FRAMING MEMBERS. SIGNIFICANT NOTCHES CONFORMING TO PART 4 MAY BE REVIEWED AND REJECTED IF THEY COMPROMISE THE STRUCTURAL INTEGRITY.
- 15. UNLESS OTHERWISE NOTED, ALL COMPONENTS OF BUILT UP MEMBERS TO BE CONTINUOUS FOR FULL SPAN. DO NOT SPLICE OR USE BUTT JOINTS.
- 16. UNLESS OTHERWISE NOTED, ALL PLIES OF BUILT-UP BEAMS ARE TO BE FASTENED WITH A DOUBLE 6. THE CONTRACTOR SHALL HAVE ON SITE ALL SURPLUS MATERIALS AND COMPLY WITH ALL LAWS ROW OF 75MM (3") LONG COMMON NAILS, NAILS SPACED AT 400MM (16") C/C, STARTING 200MM (8") FROM EACH END, ROWS LOCATED 50MM (2") FROM TOP AND BOTTOM EDGES. IF APPLICABLE, THIRD AND FOURTH PLIES FASTENED TO FIRST TWO IN THE SAME WAY.
- PROVIDE ROWS OF BLOCKING BETWEEN JOISTS AT MAX. 2100MM (7'-0") SPACING C/C ALONG LENGTH OF SPAN, IN ADDITION TO BLOCKING SHOWN ON DRAWINGS, UNLESS NOTED OTHERWISE.

SCHEDULE:

- CONCRETE IS SPECIFIED PER PERFORMANCE SPECIFICATION AS OUTLINED IN CAN/CSA A23.1. THE CONTRACTOR AND THE CONCRETE SUPPLIER TO MEET ALL CERTIFICATION, DOCUMENTATION, AND QUALITY CONTROL REQUIREMENTS.
- ALLOW A MINIMUM OF 3 WORKING DAYS FOR REVIEW OF EACH SUBMISSION OF SHOP DRAWINGS.

 2. THE CONTRACTOR AND THE CONCRETE SUPPLIER ARE TO ENSURE THAT THE PLASTIC AND HARDENED MIX PROPERTIES MEET SITE -THE REQUIREMENTS FOR PLACING, FINISHING, AND
 - ACHIEVING THE SPECIFIED PERFORMANCE REQUIREMENTS.
 - UNLESS NOTED OTHERWISE: A. CEMENT TO BE PORTLAND CEMENT TYPE GU UNLESS NOTED OTHERWISE OR REQUIRED BY EXPOSURE CLASS.
 - B. CONCRETE TO BE NORMAL DENSITY. C. NOMINAL SIZE OF COURSE AGGREGATE TO BE 20 (3/4").
 - PERFORMANCE REQUIREMENTS FOR CONCRETE TO BE IN ACCORDANCE WITH THE FOLLOWING

STRUCTURAL ELEMENT	COMPRESSIVE STRENGTH (MPA) 28 DAYS (SEE TABLE 2 A23.1-14), 56 DAYS FOR C1	EXPOSURE CLASS	REMARKS
GUARD PIERS AT RETAINING WALL	30	F1	-
CUT OFF WALL	35	C1	-
NOTES: N/A			

- 6. REFER TO CAN/CSA A23.1 FOR PERFORMANCE REQUIREMENTS ASSOCIATED WITH EACH OF THE SPECIFIED EXPOSURE CLASS. (IE. THE MAXIMUM WATER/CEMENT RATIO, MINIMUM COMPRESSIVE STRENGTH, AIR CONTENT, CURING REQUIREMENTS, CHLORIDE ION PENETRABILITY, AND ALTERNATE CEMENT TYPE TO MEET THE REQUIREMENTS FOR THE NOTED EXPOSURE CLASS.)
- 7. PLACE CONCRETE IN A MANNER TO AVOID SEGREGATION. VIBRATE ALL CONCRETE.
- 8. IMPLEMENT COLD WEATHER CONCRETING METHODS IN ACCORDANCE WITH CAN/CSA-A23.1. PROTECT CONCRETE FROM FREEZING. DO NOT PLACE CONCRETE AGAINST FROZEN GROUND.
- 9. IMPLEMENT HOT WEATHER CONCRETING METHODS IN ACCORDANCE WITH CAN/CSA-A23.1.PROTECT CONCRETE FROM EXCESSIVE HEAT AND DRYING.

FOUNDATIONS

- THE STRUCTURAL DESIGN IS BASED ON THE GEOTECHNICAL REPORT PREPARED BY: GEOTECHNICAL FIRM: ST. LAWRENCE TESTING & INSPECTION CO. LTD. REPORTINTERNAL PROJECT NUMBER: 21C012
- DATED: JANUARY 25, 2021 2. UNLESS INDICATED ON DRAWINGS, REFER TO THE GEOTECHNICAL REPORT FOR INFORMATION ON SOIL/SUBGRADE CONDITIONS, RECOMMENDATIONS FOR FOUNDATION CONSTRUCTION, AND FOR 3. BATTER OR OFFSET OF 50MM BETWEEN COURSES, ADJUST TO SUIT LARGER STONES IF
- ALL EARTHWORK INCLUDING EXCAVATION, BACKFILL, AND SUBGRADE PREPARATION. THE ASSUMED SOIL BEARING RESISTANCE AT FOOTING LEVEL:
- ULS (ULTIMATE LIMIT STATES DESIGN): 150 KPa SLS (SERVICEABILITY LIMIT STATES DESIGN): 100 KPa WITH COMPACTED ENGINEERED BACKFILL ABOVE NATIVE UNDISTURBED SOIL
- 4. BEARING SURFACE TO BE APPROVED BY THE GEOTECHNICAL CONSULTANT PRIOR TO CONSTRUCTING FOOTINGS OR LAYING ARMOR STONE BLOCKS OF THE RETAINING WALL.
- 5. REFER TO DETAILS FOR FOOTING AND FOUNDATION DESIGN.
- 7. PRIOR TO EXCAVATION, LOCATE ALL EXISTING UNDERGROUND SERVICES.
- 8. DO NOT USE EARTH FORMS UNLESS APPROVED IN WRITING. FOR ELEMENTS CAST AGAINST SOIL, INSTALL BOTTOM STEEL OF CONCRETE STRUCTURAL ELEMENT TO OBTAIN 75MM (3") CONCRETE
- FOR ELEMENTS THAT ARE TO BE BACKFILLED ON BOTH SIDES, PLACE BACKFILL SIMULTANEOUSLY ON BOTH SIDES SUCH THAT HEIGHTS DO NOT VARY BY MORE THAN 300 (12") FROM ONE SIDE TO
- 10. COMPACTION TESTING TO BE UNDERTAKEN AT ALL LOCATIONS REQUIRING COMPACTION (WHEREVER MENTIONED TO A CERTAIN % OF SPMDD) TO ENSURE SOIL AND BACKFILL ARE ADEQUATELY COMPACTED.

EXCAVATION

- 1. BEFORE EXCAVATION, CONTRACTOR IS TO VERIFY THE EXISTENCE OF PUBLIC SERVICES. FOR CONDUITS OR SERVICES WHICH INTERFERE WITH THE EXECUTION OF WORK, THE CONTRACTOR IS

 8. SNOW: RESPONSIBLE TO PROTECT AND TEMPORARILY SUPPORT FOUND UTILITIES.
- THE CONTRACTOR IS TO ENGAGE WITH THEIR OWN EXPERTS TO DETERMINE ANY DIFFICULTIES AND METHODS OF EXCAVATION, AND TO ASSUME THE COSTS INCURRED IN CONSTRUCTION AND HANDLING OF EXCAVATION SLOPES AS REQUIRED TO ENSURE THEIR STABILITY
- CARRY OUT EXCAVATION WORK FOLLOWING RECTILINEAR CONTOURS, LEAVING SUFFICIENT SPACE FOR THE CONSTRUCTION OF RETAINING WALLS, AND MAINTAIN SLOPE STABILITY FOLLOWING THE REQUIREMENTS OF OSHA.
- 4. ALL FOUNDATIONS MUST REST ON NON-ORGANIC NATURAL SOIL. THE SOIL AT THE BASE OF
- EXCAVATIONS MUST THEREFORE BE DRY, AND FREE OF DEBRIS AND ORGANIC MATERIAL. 5. REMOVE WATER FROM THE BOTTOM OF EXCAVATIONS AND KEEP PUMPS AVAILABLE.
- CONCERNING THE MANAGEMENT OF EXCAVATED MATERIALS. THE CONTRACTOR SHOULD PROVIDE

COSTS RELATED TO THE APPLICATION OF THESE LAWS SEPARATE FROM OTHER ITEMS OF THE

FOOTING PAD NOTES

- 1. PROVIDE ENGINEERED FILL FOOTING PAD AS PER CROSS SECTION
- 2. SUBGRADE BELOW PAD TO BE ASSESSED AND APPROVED BY A QUALIFIED GEOTECHNICAL ENIGNEER PRIOR TO PLACEMENT, ANY TOPSOIL, LOOSE, WET OR DISTURBED SOIL IS TO BE REMOVED WITH PAD MATERIAL
- 3. PAD TO EXTEND OVER FULL WIDTH OF RAMP RETAINING WALLS PLUS AN ADDITIONAL 300MM ON
- 4. PAD TO EXTEND 300MM BEYOND EDGES OF BOTTOM OR FOUNDATION BLOCK BOTH IN FRONT OF AND BEHIND WALL
- PAD TO HAVE A MINIMUM THICKNESS OF 300MM
- 6. PAD TO BE COMPOSED OF GRANULAR A COMPACTED TO 100% SPMDD

DRAINAGE LAYER NOTES (TYP. FOR ALL WALLS)

- 1. LAYER TO BE 300MM THICK, LOCATED IMMEDIATELY BEHIND BOTTOM BLOCK/ COURSE
- 2. TO BE COMPOSED OF 19MM OPSS CLEAR CRUSHED STONE
- 3. TO BE PROVIDED WITH A 100MM Ø PERFORATED PVC WEEP PIPE, BASE OF THE PIPE TO BE LOCATED AT BASE OF BOTTOM BLOCK. WEEP PIPE TO BE PROVIDED WITH 4x DISCHARGE OUTLETS THROUGH THE BOTTOM COURSE OF BLOCK (EVENLY DISTRIBUTED ALONG FULL WALL LENGTH)
- 4. DRAINAGE LAYER TO BE WRAPPED IN AN INDEPENDENT UNWOVEN GEOTEXTILE AS PER THE FOLLOWING:
- 4.1. GEOTEXILE TO MEET OPSS 1860 CLASS II REQUIREMENTS

4.2. AT ALL SEAMS, THE GEOTEXTILE IS TO OVERLAP AT LEAST 500MM

- GENERAL ARMOR STONE NOTES
- 1. ALL ARMOR STONES (FOR RETAINING WALL) TO HAVE A CROSS-SECTION OF 400x600MM (16" x 1. ALL CONCRETE REINFORCEMENT AND STEEL WIRE USED FOR REBAR TIES TO BE GALVANIZED 24"), OR LARGER
- 2. ALL ARMOR STONES TO BE PRECAST CONCRETE OR MEDIUM OR HIGH-DENSITY STONE, MIN.
- 2340 KG/M3 (23 KN/M3)
- 4. LENGTH OF INDIVIDUAL BLOCKS OR STONES IS VARIABLE TO SUIT PROJECT NEEDS, SO LONG AS THE FOLLOWING CONSTRAINTS ARE RESPECTED:
- 4.1. NO BLOCKS MAY BE LESS THAN 500MM (20") LONG
- 4.2. BLOCKS ARE TO BE ARRANGED IN A RUNNING-BOND PATTERN WITH VERTICAL JOINTS NO 5. PROVIDE ADDITIONAL SUPPORT BARS AS REQUIRED TO PREVENT MOVEMENT OF LESS THAN 200MM (8") AWAY FROM THE VERTICAL JOINTS OF ADJACENT COURSES
- 4.3. IF THERE IS VARIABILITY IN BLOCK/STONE SIZE, USE LARGER BLOCKS FOR LOWER COURSES, ABOVE GRADE, IN AREA WITH TALLEST WALL (COURSE 3, NEAR ESCARPMENT)

DESIGN LOADS

THE VALUES FOR CLIMATIC DATA USED IN THE DETERMINATION OF DESIGN LOADS HAVE BEEN OBTAINED FROM THE 2015 NBCC FOR THE SPECIFIC LOCATION OF PERTH, ON.

SUPERIMPOSED DEAD LOADS (SDL) ARE NON-STRUCTURAL DEAD LOADS DUE TO NON-STRUCTURAL TOPPINGS,

- 2. SELF WEIGHT (SWT) IS DUE TO THE WEIGHT OF THE STRUCTURE ITSELF. IT VARIES WITH THE STRUCTURAL SYSTEM.
- FINISHES, PARTITIONS, ROOFING MATERIALS, SUSPENDED EQUIPMENT, PAVERS, SOIL, ETC. 4. DEAD LOAD (DL) IS THE SELF WEIGHT OF THE STRUCTURE PLUS THE SUPERIMPOSED DEAD LOAD.
- GRAVITY LOADS ARE SHOWN ON PLANS.
- 6. UNLESS OTHERWISE NOTED, DESIGN LOADS SHOWN ARE SPECIFIED (UNFACTORED) LOADS, TO BE USED FOR ULS
- 7. <u>LIVE:</u>
- 4.8 KPa (ASSEMBLY OCCUPANCY) LOAD BOARDWAK SUPERIMPOSED LIVE LOAD ON PATHWAY FOR RETAINING WALL DESIGN: 4.8 KPa
- SNOW LOAD ON GROUND SURFACE:
- SELF-WEIGHT OF BOARDWALK FOR DESIGN PURPOSES: 0.6 KPa
- SNOW LOADS DO NOT EXCEED LIVE LOADS
- 10. PARAMETERS USED IN RETAINING WALL STRUCTURAL ANALYSIS:
- DENSITY, Y = 22 KN/M3 10.1.2. ANGLE OF INTERNAL FRICTION, ϕ ef = 38°
- 10.2. ACTIVE SOIL PRESSURE COEFFICIENT, Ka = 0.31
- SEISMIC PARAMETERS: PGA = 0.302, Kh = 0.3, Kv = 0.3, PGA APPLIED AT 0.33H 10.4. SLIDING COEFFICIENT OF FRICTION BETWEEN BLOCKS: $\mu = 0.533$

CONCRETE REINFORCEMENT

- AS PER CSA G-164-M92: 610G/M2
- 2. REINFORCEMENT TO CONFORM TO THE FOLLOWING STANDARDS:
- DEFORMED BARS CAN/CSA G30.18, GRADE 400W, WHERE REBAR IS SHOWN TO BE WELDED USE GRADE 400W. 3. BARS MARKED CONTINUOUS TO BE TERMINATED IN STANDARD HOOKS AT ENDS WHICH
- EXTEND TO FAR FACE OF ELEMENT AND SPLICED USING CLASS B LAPS.
- 4. ALL REBAR HOOKS TO BE STANDARD LENGTH 90° OR 180° HOOKS. REBAR LENGTHS LISTED ON DRAWINGS DO NOT INCLUDE THE HOOK LENGTH. REFER TO RISC MANUAL OF STANDARD PRACTICE FOR STANDARD HOOKS.
- REINFORCEMENT DURING CONSTRUCTION AND WHEN PLACING CONCRETE. 6. PROVIDE SUFFICIENT SUPPORT TO MAINTAIN SPECIFIED CONCRETE COVER.

UNHEATED AREAS

2. LARGEST COVER REQUIRED GOVERNS


- 7. ALL REINFORCING TO BE CLEAN, FREE OF LOOSE SCALE, OIL, DIRT, RUST, AND ANY OTHER SUBSTANCE THAT MAY AFFECT BONDING CAPACITY.
- 8. MINIMUM CLEAR CONCRETE COVER TO REINFORCEMENT CLOSEST TO THE SURFACE TO BE AS TABULATED BELOW UNLESS NOTED OTHERWISE ON THE DRAWINGS:

STRUCTURAL ELEMENT	EXPOSED		
BOTTOM OF CUT OFF WALL	75 (3")		
SIDES OF CUT OFF WALL	60 (2-3/8")		
TOP OF CUT OFF WALL	50 (2")		
NOTES: 1. EXPOSED MEANS IN DIRECT CONTACT WITH EARTH AND/OR WEATHER, OR IN			



THE POSITION OF POLE LINES. CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWING, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

DESIGN PROFESSIONAL'S SEAL OR SIGNATURE IS EFFECTIVE ONLY AS TO THAT VERSION OF THIS DOCUMENT AS ORIGINALLY PUBLISHED BY DESIGN PROFESSIONAL. DESIGN PROFESSIONAL IS NOT RESPONSIBLE FOR ANY SUBSEQUENT MODIFICATION. CORRUPTION. OF UNAUTHORIZED USE OF SUCH DOCUMENT. TO VERIFY THE VALIDITY OR APPLICABILITY OF THE SEAL OR SIGNATURE, CONTACT DESIGN PROFESSIONAL.



ISSUED FOR 90% REVIEW 2022-11-11 T.P./ Y.H. ISSUED FOR 50% REVIEW 2022-10-07 T.P./ Y.H. YYYY-MM-DD DSGN/DRFT REVISION COMMENTS

SNCA - FINDLAY CREEK BOARDWALK OTTAWA, ONTARIO

STRUCTURAL NOTES, KEY PLAN,




Phone: (613)828-7800, Fax: (613)828-2600 DESIGNED: TP PROJECT No.: 22-1042A DRAFTED: YH REVISION DATE: 2022-09-22 CHECKED: TP APPROVED: TP REVISION No.: 0

S001

CLIENT REF No.: XX-2022-09

Phone: (613)735-2507, Fax:(613)735-4513 1150 MORRISON DRIVE, SUITE 410, OTTAWA, ON

2-1042A - SNCA - FINDLAY CREEK BOARDWALK- STRUCTURAL.DWG



- FASTEN RAIL TO POST: 2x 3" LONG WOOD SCREWS (TYP.) — 2x2 PICKETS, FASTEN TO PICKET SPACING; 125 (5") RAILS FOR Vf = 0.5 KN S002 MAX. POST SPACING: 1200 (4') - FASTEN RAIL TO POST: 2x 3" LONG WOOD SCREWS (TYP.) — POSTS MAY BE DISTRIBUTED — BOLTS THROUGH INTERNAL JOISTS, BEHIND AS NEEDED (SUCH AS EQUAL - BLOCKING, BEHIND EDGE JOIST (TYP.) SUPPORT FIXTURE -SUPPORT FIXTURE MAX. SPACING BETWEEN SUPPORTS: 3505 (11'6") BY PILE MANUFACTURER BY PILE MANUFACTURER - 1/2"Ø BOLTS (x2) WITH WASHERS 1/2"Ø BOLTS (x2) WITH WASHERS -ORIGINAL GRADE — OPTIONAL DESIGN ALTERNATIVES: IF 2x12 JOISTS ARE USED, MAX. SPACING INCREASE TO 3960 (13') LEVEL (APPROX.) IF 2x8 JOISTS ARE USED, MAX. SPACING REDUCE TO 2740 (9')

BOARDWALK WITH GUARD, ELEVATION (TYP.)

— 2x3 BUMPER (TYP.) ___ 2-PLY JOIST AT EDGES (TYP.) - 2x10 JOISTS (TYP.), TO COVER FULL IN ADDITION TO BLOCKING IN NOTES - INSTALL -SPAN PLUS AN ADDITIONAL 150MM BLOCKING BETWEEN JOISTS AT EDGES, EXT TO (6") BEYOND FOR BOLT OVERLAP BOLTS FROM EACH POST, SECURE BLOCKING - 1-1/4" x 5-1/4" NOM. DECK BOARDS, WITH 3x 3" LONG NAILS ON EACH SIDE FASTENED WITH GALV. DECK SCREWS AT EACH INTERSECTION — 1/2" Ø GALV. BOLT FASTENING JOISTS WITH THOSE OF ADJACENT SPAN, CENTERED OVER BEAM, CENTERED VERTICALLY IN JOIST - JOISTS FROM OPPOSING SPAN — FASTEN ONE JOIST (NOT BOTH) TO BEAM WITH HGA10 TIE, OR 4x DIAGONAL, PRE-DRILLED, 3" LONG WOOD SCREWS (2 FROM EACH DIRECTION) (TYP.) 1730

— BOLTS THROUGH INTERNAL JOISTS, BEHIND - BLOCKING, BEHIND EDGE JOIST (TYP.) - SECURE BEAM TO CONCRETE BLOCK WITH 1x HGA10 TIES ON EACH SIDE (2x PER BLOCK, 4x PER BEAM), SUPPORT FIXTURE~ SUPPORT FIXTURE USE TAPCON CONCRETE SCREWS INTO BLOCK (TYP.) MAX. SPACING BETWEEN SUPPORTS: 3505 (11'6") BY PILE MANUFACTURER BY PILE MANUFACTURER - 1/2"Ø BOLTS (x2) WITH WASHERS — 1/2"Ø BOLTS (x2) WITH WASHERS OPTIONAL DESIGN ALTERNATIVES:

• IF 2x12 JOISTS ARE USED, MAX. SPACING INCREASE TO 3960 (13') ORIGINAL GRADE — LEVEL (APPROX.) • IF 2x8 JOISTS ARE USED, MAX. SPACING REDUCE TO 2740 (9')

BOARDWALK WITHOUT GUARD, SECTION (TYP.)
SCALE: 1:10

NOTE: CONSTRUCT AS PER DETAIL 1, 2/S002 FOR BOARDWALK WITH GUARD, CONSTRUCT AS PER DETAIL 3, 4/S002 FOR BOARDWALK WITHOUT GUARD. REFER TO CIVIL DRAWINGS FOR LOCATIONS WHERE A GUARD IS REQUIRED.

BOARDWALK WITHOUT GUARD, ELEVATION (TYP.)

SCALE: 1:10

SNCA - FINDLAY
CREEK BOARDWALK
OTTAWA, ONTARIO

ISSUED FOR 90% REVIEW

ISSUED FOR 50% REVIEW

REVISION COMMENTS

SOUTH NATION

STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

PROJECT LOCATION $^{\perp}$

KEY PLAN SCALE: NTS

2022-11-11 T.P./ Y.H.

2022-10-07 T.P./ Y.H.

No. YYYY-MM-DD DSGN/DRFT

KEYPLAN (NTS)

DE LA NATION SUD

THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWING, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND

DESIGN PROFESSIONAL'S SEAL OR SIGNATURE IS EFFECTIVE ONLY AS TO THAT VERSION OF THIS DOCUMENT AS ORIGINALLY PUBLISHED BY DESIGN PROFESSIONAL. DESIGN PROFESSIONAL IS NOT RESPONSIBLE FOR ANY SUBSEQUENT MODIFICATION, CORRUPTION, OR UNAUTHORIZED USE OF SUCH DOCUMENT. TO VERIFY THE VALIDITY OR APPLICABILITY OF THE SEAL OR SIGNATURE, CONTACT DESIGN PROFESSIONAL.

CONSERVATION

BOARDWALK TYP. SECTIONS




12 INTERNATIONAL DRIVE, PEMBROKE, ON Phone: (613)735-2507, Fax:(613)735-4513 1150 MORRISON DRIVE, SUITE 410, OTTAWA, ON Phone: (613)828-7800, Fax: (613)828-2600

DESIGNED: TP		PROJECT No.:	22-1042A
DRAFTED: YH		REVISION DATE:	2022-09-22
CHECKED: TP	APPROVED:	REVISION No.:	
SCALE:		CLIENT REF No.:	XX-2022-09

S002


2-1042A - SNCA - FINDLAY CREEK BOARDWALK- STRUCTURAL.DWG



SOUTH NATION CONSERVATION DE LA NATION SUD

THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWING, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

DESIGN PROFESSIONAL'S SEAL OR SIGNATURE IS EFFECTIVE ONLY AS TO THAT VERSION OF THIS DOCUMENT AS ORIGINALLY PUBLISHED BY DESIGN PROFESSIONAL. DESIGN PROFESSIONAL IS NOT RESPONSIBLE FOR ANY SUBSEQUENT MODIFICATION, CORRUPTION, OR UNAUTHORIZED USE OF SUCH DOCUMENT. TO VERIFY THE VALIDITY OR APPLICABILITY OF THE SEAL OR SIGNATURE, CONTACT DESIGN PROFESSIONAL.



KEY PLAN SCALE: NTS KEYPLAN (NTS)

ISSUED FOR 90% REVIEW

ISSUED FOR 50% REVIEW

REVISION COMMENTS

SNCA - FINDLAY CREEK BOARDWALK OTTAWA, ONTARIO

TYP. SLOPE SECTIONS, **BUMP OUTS PLAN & SECTION**




12 INTERNATIONAL DRIVE, PEMBROKE, ON Phone: (613)735-2507, Fax:(613)735-4513 1150 MORRISON DRIVE, SUITE 410, OTTAWA, ON Phone: (613)828-7800, Fax: (613)828-2600

PROJECT No.: 22-1042A DRAFTED: YH REVISION DATE: 2022-09-22 REVISION No.: CHECKED: TP APPROVED: CLIENT REF No.: XX-2022-09

S003

22-1042A - SNCA - FINDLAY CREEK BOARDWALK- STRUCTURAL.DWG



SOUTH NATION CONSERVATION DE LA NATION SUD

THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWING, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

DESIGN PROFESSIONAL'S SEAL OR SIGNATURE IS EFFECTIVE ONLY AS TO THAT VERSION OF THIS DOCUMENT AS ORIGINALLY PUBLISHED BY DESIGN PROFESSIONAL. DESIGN PROFESSIONAL IS NOT RESPONSIBLE FOR ANY SUBSEQUENT MODIFICATION, CORRUPTION, OR UNAUTHORIZED USE OF SUCH DOCUMENT. TO VERIFY THE VALIDITY OR APPLICABILITY OF THE SEAL OR SIGNATURE, CONTACT DESIGN PROFESSIONAL.

PROJECT LOCATION - REPART OF THE PROJECT LOCATION - REPART OF THE

KEYPLAN (NTS)

KEYPLAN (NI

5			
4			
3			
2	2022-11-11	T.P./ Y.H.	ISSUED FOR 90% REVIEW
1	2022-10-07	T.P./ Y.H.	ISSUED FOR 50% REVIEW
No.	YYYY-MM-DD	DSGN/DRFT	REVISION COMMENTS

SNCA - FINDLAY CREEK BOARDWALK OTTAWA, ONTARIO

FRAMING PLAN AT BOARDWALK
VIEWING PLATFORM




12 INTERNATIONAL DRIVE, PEMBROKE, ON Phone: (613)735-2507, Fax:(613)735-4513 1150 MORRISON DRIVE, SUITE 410, OTTAWA, ON Phone: (613)828-7800, Fax: (613)828-2600


DESIGNED: TP		PROJECT No.:	22-1042A
DRAFTED: YH		REVISION DATE:	2022-09-22
CHECKED: TP	APPROVED:	REVISION No.:	
SCALE:		CLIENT REF No.:	XX-2022-09

S004


22-1042A - SNCA - FINDLAY CREEK BOARDWALK- STRUCTURAL.DWG

FRAMING PLAN AT BOARDWALK VIEWING PLATFORM
SCALE: 1:20






LEGEND



PROPOSED **DECIDUOUS TREE** REFER TO DETAIL 1



PROPOSED **CONIFEROUS TREE** REFER TO DETAIL 1

TOPSOIL AND SOD REINSTATEMENT

REMOVE DAMAGED OR OBJECTIONABLE BRANCHES, FOLLOW THE MOST

RECENT CANADIAN NURSERY &

DO NOT PRUNE LEADER

REMOVE AFTER PLANTING

AROUND TREE BASE

CONSTRUCT 100mm SAUCER

CUT AND REMOVE BURLAP AND

WIRE BASKET FROM TOP 2/3

OF ROOT BALL WITHOUT DISTURBING ROOTS

REMOVE DAMAGED OR OBJECTIONABLE BRANCHES, FOLLOW THE MOST RECENT

NOT PRUNE LEADER.

AROUND TREE BASE.

CANADIAN NURSARY & TRADES ASSOCIATION PRACTICE. DO

CONSTRUCT 100mm SAUCER

CUT AND REMOVE BURLAP

OUTSIDE EDGE OF THE TREE BASE

TREE PROTECTION

SIGNAGE AS PER CITY STANDARD

AND WIRE BASKET FROM TOP

2/3 OF ROOT BALL WITHOUT DISTURBING ROOTS.

TREE PLANTING

BRANCHES.

TRADES ASSOCIATION PRACTICE.

TREE WRAP APPLIED SPIRALLY FROM

GROUND UP TO HEIGHT OF SECOND

TREE PROTECTION **FENCING** REFER TO DETAIL 2

PLANT	PLANT LIST					
KEY	QTY	BOTANICAL NAME	COMMON NAME	CAL/ HT.	CONDITION/REMARKS	
DECIDUOUS TREES						
Ar	2	Acer rubrum	Red Maple	50 mm Cal	Wire Basket	
Qb	1	Quercus bicolor	Swamp White Oak	50 mm Cal	Wire Basket	
Qm	1	Quercus macrocarpa	Burr Oak	50 mm Cal	Wire Basket	
CONIFER	ROUS TF	REES				
Ps	3	Pinus strobus	Eastern White Pine	200 cm ht.	Wire Basket	
То	4	Thuja occidentalis	Eastern White Cedar	200 cm ht.	Wire Basket	

PLANTING NOTES

MINIMUM 1 STAKE 2400mm LONG ON WINDWARD SIDE. SECURE

RUBBER HOSE, ALLOWING SLACK IN GALVANIZED WIRE. REMOVE STAKES AFTER ONE YEAR. STAKE BEYOND EDGE OF ROOT BALL

WITH No. 12 GALVANIZED WIRE ENCASED IN 12mm DIAMETER

ROOT COLLAR TO BE SET 100mm ABOVE FINISHED GRADE

APPLY APPROVED PLASTIC

RODENT GUARD 450mm MINIMUM

2. LOCATION AS SPECIFIED ON THE

CONTRACT DRAWINGS

MINIMUM 1 STAKE 2400mm LONG ON WINDWARD SIDE. SECURE WITH No. 12 GALVANIZED WIRE ENCASED IN 12mm DIAMETER

RUBBER HOSE, ALLOWING SLACK IN GALVANIZED WIRE. REMOVE STAKES AFTER ONE YEAR. STAKE BEYOND EDGE OF ROOT BALL

ALL MEASUREMENTS ARE IN MILLIMETRES

UNLESS OTHERWISE NOTED

2. LOCATION AS SPECIFIED ON THE

CONTRACT DRAWINGS

ROOT COLLAR TO BE SET 100mm ABOVE FINISHED GRADE

TOPSOIL MIXTURE AS PER SPECIFICATION

1. ALL MEASUREMENTS ARE IN MILLIMETRES

TOPSOIL MIXTURE AS PER SPECIFICATION

THE PROPERTY OF THE PROPERTY O

DECIDUOUS TREE PLANTING

CONIFEROUS TREE PLANTING


COMPACTED SUBGRADE

- 1. THE CONTRACTOR SHALL VERIFY AND LOCATE ALL EXISTING SERVICES / UTILITIES IN THE FIELD PRIOR TO ANY CONSTRUCTION.
- 2. REFER TO ENGINEERING DRAWINGS FOR ALL REMOVALS.
- 3. THE CONTRACTOR SHALL INSTALL AND MAINTAIN TREE PROTECTION FENCING AS NOTED ON THE DRAWINGS DURING CONSTRUCTION PHASE.
- ALL LAYOUT FOR PROPOSED PLANT MATERIAL TO BE STAKED BY THE CONTRACTOR AND VERIFIED AND APPROVED BY PROJECT MANAGER PRIOR TO ANY PLANTING.
- REPORT ANY DISCREPANCIES PRIOR TO COMMENCING WORK. NO RESPONSIBILITY IS BORNE BY THE OWNER AND PROJECT MANAGER FOR UNKNOWN SUBSURFACE CONDITIONS.
- REINSTATE ALL AREAS AND ITEMS THAT ARE DAMAGED ON SITE AND REPORT ANY ERRORS AND/OR OMISSIONS TO THE PROJECT MANAGER.
- WITH THE EXCEPTION OF THE CITY OF OTTAWA CONSTRUCTION SPECIFICATION & STANDARD DETAILS, THE ONTARIO PROVINCIAL STANDARDS (OPSD) & STANDARD SPECIFICATIONS (OPSD) SHALL APPLY.
- 8. THIS DRAWING IS TO BE READ AND INTERPRETED IN CONJUNCTION WITH THE CONTRACT DRAWINGS AND SPECIFICATIONS.
- 9. ALL PLANT MATERIAL SHALL BE NURSERY GROWN STOCK UNLESS OTHERWISE NOTED.
- 10. DECIDUOUS TREES TO HAVE A MINIMUM 1800 CLEAR STEM ABOVE GRADE.
- 11. ALL PLANT MATERIAL SHALL BE WARRANTIED FOR TWO YEARS FROM THE DATE OF PERFORMANCE ACCEPTANCE AS DETERMINED BY THE PROJECT MANAGER.
- 12. ALL STEEL STAKING POSTS FOR TREES ARE TO BE REMOVED AFTER ONE GROWING SEASON UNLESS OTHERWISE DIRECTED BY THE PROJECT MANAGER.
- 13. ANY PROPOSED PLANT MATERIAL SUBSTITUTIONS SHALL BE MADE WITH PLANTS OF EQUIVALENT OVERALL FORM, HEIGHT, HABIT, FLOWER, LEAF. COLOUR AND CULTURE AND ONLY AFTER WRITTEN APPROVAL FROM THE PROJECT MANAGER.



AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWING, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, THE CONTRACT SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

DESIGN PROFESSIONAL'S SEAL OR SIGNATURE IS EFFECTIVE ONLY AS TO THAT VERSION OF THIS DOCUMENT AS ORIGINALLY PUBLISHED BY DESIGN PROFESSIONAL. DESIGN PROFESSIONAL IS NOT RESPONSIBLE FOR ANY SUBSEQUENT MODIFICATION, CORRUPTION, OR JNAUTHORIZED USE OF SUCH DOCUMENT. TO VERIFY THE VALIDITY OR APPLICABILITY OF THE SEAL OR SIGNATURE, CONTACT DESIGN PROFESSIONA



KEYPLAN (NTS)

GENERAL NOTES:

ALL GENERAL SITE INFORMATION AND CONDITIONS ARE COMPILED FROM CONSULTANT'S FIELD NOTES AND PLANS PROVIDED BY THE OWNER. REPORT ANY DISCREPANCIES PRIOR TO COMMENCING WORK, NO

RESPONSIBILITY IS BORN BY THE CONSULTANTS FOR UNKNOWN UTILITIES OR CHECK AND VERIFY ALL DIMENSIONS ON SITE AND REPORT ANY ERRORS AND/OF

OMISSIONS TO THE PROJECT MANAGER REINSTATE ALL AREAS AND ITEMS DAMAGED AS A RESULT OF CONSTRUCTION

ACTIVITIES TO THE SATISFACTION OF THE PROJECT MANAGER. INDIVIDUAL UTILITY AGENCIES MUST BE CONTACTED TO VERIFY AND LOCATE AL PUBLIC AND PRIVATE UTILITIES, MARK ON SITE AND RETAIN CLEARANCE

DOCUMENTATION. THE DRAWINGS AND DETAILS ARE IN PART DIAGRAMMATIC AND INTENDED TO

CONVEY THE DESIGN. THE CONTRACTOR IS TO COORDINATE ACCESS. TRAFFIC CONTROL AND PROTE THE GENERAL PUBLIC AND USERS OF THE SITE WITH APPROPRIATE CONTROL FENCING AND SUPERVISION THROUGHOUT THE CONSTRUCTION PERIOD, TO TH SATISFACTION OF THE FACILITY MANAGER AND THE PROJECT MANAGER.

1	2022-11-11	KC	ISSUED FOR 90% REVIEW	
No.	YYYY-MM-DD	BY	REVISION COMMENTS	

FINDLAY CREEK BOARDWALK EXTENSTION OTTAWA, ONTARIO

LANDSCAPE PLAN



12 INTERNATIONAL DRIVE, PEMBROKE, ON Phone: (613)735-2507, Fax:(613)735-4513 1150 MORRISON DRIVE, SUITE 410, OTTAWA, ON

Phone: (613)828-7800, Fax: (613)828-2600

CLIENT No.: XX SCALE: AS NOTED DESIGNED: K. CERVENY DRAFTED: K. SELIN

Jp2g Project No.: 22-1042A

CHECKED: K. CERVENY APPROVED: K. CERVENY

NDSCAPE PLAN 22-11-11.DWG

landscape architecture

TREE PROTECTION REQUIREMENTS:

1. PRIOR TO ANY WORK ACTIVITY WITHIN THE CRITICAL ROOT ZONE (CRZ = 10) TREE PROTECTION X DIAMETER) OF A TREE, TREE PROTECTION FENCING MUST BE INSTALLED SURROUNDING THE CRITICAL ROOT ZONE, AND REMAIN IN PLACE UNTIL THE WORK IS COMPLETE.

FENCING AS PER

COMPACTED SUBGRADE

2. UNLESS PLANS ARE APPROVED BY CITY FORESTRY STAFF, FOR WORK WITHIN THE CRZ: - DO NOT PLACE ANY MATERIAL OR EQUIPMENT - INCLUDING - DO NOT ATTACH ANY SIGNS. NOTICES OR POSTERS TO ANY TREE: - DO NOT RAISE OR LOWER THE EXISTING GRADE; - TUNNEL OR BORE WHEN DIGGING:

- DO NOT DAMAGE THE ROOT SYSTEM, TRUNK, OR BRANCHES OR ANY ENSURE THAT EXHAUST FUMES FROM ALL EQUIPMENT ARE NOT DIRECTED TOWARD ANY TREE CANOPY. - DO NOT EXTEND HARD SURFACE OR SIGNIFICANTLY CHANGE

3. TREE PROTECTION FENCING MUST BE AT LEAST 1.2M IN HEIGHT, AND CONSTRUCTED OF RIGID OR FRAMED MATERIALS (E.G. MODULOC - STEEL, PLYWOOD HOARDING, OR SNOW FENCE ON A 2"X4" WOOD FRAME) WITH POSTS 2.4M APART, SUCH THAT THE FENCE LOCATION CANNOT BE ALTERED. ALL SUPPORTS AND BRACING MUST BE PLACED OUTSIDE OF THE CRZ, AND INSTALLATION MUST MINIMISE DAMAGE TO EXISTING ROOTS.

4. THE LOCATION OF THE TREE PROTECTION FENCING MUST BE DETERMINED BY AN ARBORIST AND DETAILED ON ANY ASSOCIATED PLANS FOR THE SITE (E.G. TREE CONSERVATION REPORT, TREE DISCLOSURE REPORT, ETC), THE PLAN AND CONSTRUCTED FENCING MUST BE APPROVED BY CITY FORESTRY STAFF PRIOR TO THE COMMENCEMENT OF WORK. 5. IF THE FENCED TREE PROTECTION AREA MUST BE REDUCED TO FACILITATE CONSTRUCTION, MITIGATION MEASURES MUST BE PRESCRIBED BY AN

ARBORIST AND APPROVED BY CITY FORESTRY STAFF. THESE MAY INCLUDE THE PLACEMENT OF PLYWOOD, WOOD CHIPS, OR STEEL PLATING OVER THE ROOTS FOR PROTECTION OR THE PROPER PRUNING AND CARE OF ROOTS WHERE ENCOUNTERED. ALL CITY-OWNED TREES ARE PROTECTED UNDER THE MUNICIPAL TREES AND

NATURAL AREAS PROTECTION BY-LAW (2006-279). WITHIN THE URBAN AREA, PRIVATELY-OWNED TREES GREATER THAN 50CM DIAMETER ON LOTS 1HA IN SIZE OR LESS, AND TREES GREATER THAN 10CM DIAMETER ON LOTS >1HA, ARE PROTECTED UNDER THE URBAN TREE CONSERVATION BY-LAW

TREE PROTECTION FENCING

SOIL AND ROOT DISTURBANCE NOT PERMITTED ———